

数 量 総 括 表									
-----------	--	--	--	--	--	--	--	--	--

[illegible]

[illegible]

計　第　　　　　表							区画線工			
								計　　　算　　　表		
測 点	距 離	外側線（右）			外側線（左）			センターライン		
				延長			延長			延長
No.0										
No.1	20.0						20.0			
No.2	20.0						20.0			
No.3	20.0						20.0			
No.4	20.0						20.0			
No.5	20.0						20.0			
N0.6	20.0						20.0			
N0.7	20.0						20.0			
N0.8	20.0						20.0			
N0.9	20.0						20.0			
No.10	20.0						20.0			
No.11	20.0						20.0			
No.12	20.0			20.0			20.0			20.0
No.13	20.0			20.0			20.0			20.0
No.14	20.0			20.0			20.0			20.0
	5.0			5.0			5.0			5.0
No.15	15.0			15.0			15.0			15.0
	5.0			5.0			5.0			5.0
No.16	15.0			15.0			15.0			15.0
No.17	20.0			20.0			20.0			20.0
	10.0			10.0			10.0			10.0
計	350.0			130.0			350.0			130.0

市道新町1号線舗装工事 数量計算書 交通誘導員			
工種	数量	配置人数 日当り作業量	
舗装版切断	233.8	1400	0.17
舗装版剥ぎ取り・破碎	957.6	379	2.53
路上路盤再生工	1712.1	790	2.17
表層工	1712.1	2300	0.74
区画線工 15cm	610	1000	0.61
合計			6.22
配置個所数	7	7日×3人	≒7日 21人

2

2

2